No.	Items of work	Unit	Rate	Quantity	Cost
	VII. Improvements to Bhoga Mantapam.		Rs. a. p.		Rs.
1	Excavating foundations	C.yd.	0 4 0	11	
2	Filling in foundations with cement concrete 1 : 4 : 8	C.ft.	0 7 0	92	
3	Size stone in mud	,,	0 5 0	188	
4	Burnt stone pillars $1\frac{1}{4}' \times 1\frac{1}{4}'$ roughly dressed including hoisting	R.ft.	2 0 0	54	
5	Burnt stone beams $1' \times 1'$ do	,,	1 12 0	51	
6	Conveying slabs including hoisting and fixing in cement concrete and roughly dressed 6" thick	S.ft.	1 0 0	196	
7	Slabs over retaining wall 6" thick including rougaly dressing and fixing, etc., complete over retaining wall	,,	0 8 0	68	
8	Constructing masonry Gopuram including cement plastering cornice, etc., complete	L. S.	..	..	
9	Filling the gaps with size stone in cement mortar	C.ft.	0 10 0	30	
10	Cement mortar band, at the joints of the covering slabs	R.ft.	0 3 0	160	
11	Cement pointing to basement	Sqr.	4 0 0	1·82	
12	Unforeseen charges	L. S.	..	..	
	VIII. Miscellaneous Works.				
1	Levelling the acquired area and converting it into garden including enclosing the same with fencing 1 wicket gate and providing seats, etc., complete	L. S.	..	..	
2	Providing, fixing burnt stone slabs paving in the prakaram of Sri Rameswara Temple	S.ft.	0 4 0	1,150	
3	Repairing the existing damaged stone retaining wall height 3' to 6'	R.ft.	0 12 0	332	
4	Underpinning and other unforeseen works such as dismantling the damaged portions and conveying materials and other charges	L. S.	..	..	

D. A. HUKERI,
Executive Engineer.

CHITALDRUG DIVISION.

Abstract Notification dated 14th July 1939.

The attention of the public is invited to the Notification calling for tenders for raising the weirs, constructing lifting dam across the weir halla and other works of Chikkamadhure tank, published in the *Mysore Gazette*, dated 20th July 1939, Part VI, pages 1393-1396.

The last date of receiving tenders is 5th August 1939.

S. RAMASWAMY,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS

OFFICE OF THE INSPECTOR-GENERAL OF POLICE IN MYSORE, BANGALORE.

Notice No. T. C. 295—37-38, dated 19th November 1937.

The public are hereby informed that an Avery's Weigh-bridge to weigh motor vehicles is erected in the Office of the Inspector-General of Police in Mysore, Cenotaph Road, Bangalore City, and that motor vehicles brought for weighment will be weighed on payment of a fee of Rs. 10 for each weighment. A certificate of weighment will invariably be issued with each weighment so made.

F. A. HAMILTON,
Inspector-General of Police.

OFFICE OF THE SUPERINTENDENT, GOVERNMENT PRINTING, BANGALORE.

Abstract Notification dated 18th July 1939.

The attention of the public is invited to the detailed notice, dated 7th July 1939, published on page 1345 of Part VI of the *Mysore Gazette*, dated 13th July 1939, regarding the sale by public auction of unserviceable articles at the Government Branch Press, Mysore, on Friday the 4th August 1939, at 3 P.M.

B. KRISHNASWAMY CHETTY,
Ag. *Superintendent.*